UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 28.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 03**.09.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 03.09.2025 upto 12.00 PM

Opening of Quotations:- 03.09.2025 at 12.00 PM

S.No	Name of the work	EstimatedCost
1	Maintenance of Buildings-:"Replacement of EWC at Hostel-E(NRS)" in UoH Campus.	Rs. 20,650.74/-

Executive Engineer A/C

Name of work: Maintenance of Building:- Replacement of EWC at Hostel-E (NRS)" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.** **3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.** **4) The HSN Code for each item should be indicated.**						
SCHEDULE OF QUANTITIES						
S.No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	1.80 Sqm	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
2	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.00 Cum	Cum	Figure: Rs_____ Words: Rupees_____ _____	
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.36 Cum	Cum	Figure: Rs_____ Words: Rupees_____ _____	
4	11.37A	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kgper sqm including pointing the joints with white cement mixed with pigment of matching shade complete.	1.65 Sqm	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
5	14.82	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	

6	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
7	18.53A	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge	3.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
8	18.76	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay F.P.S. (non modular) bricks	2.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
9	18.53.1	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15mm nominal bore	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
10	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
11	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 100 mm outlet Sand Cast Iron S&S as per IS: 1729.	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
12	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for				

		thermal expansion, (i) Single socketed pipes.				
	12.41.1	75mm diameter	3.00 Rmt	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	12.41.2	110mm diameter	3.00 Rmt	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
13	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion				
	a/12.42.5.1	bend 87.5	2.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
	b/12.42.5.2	110mm bend	29 .00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
14	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall 20 mm nominal outer dia. Pipes.	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
15	18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc.	5.00 Rmt	Rmt	Figure: Rs_____ Words: Rupees_____	

		complete : 25 to 40 mm nominal bore			_____	
16	MR	Providing and fixing of C.P Health faucet Make:Jaquar 15mmdia	1.00 Each	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount (excluding GST)**_____ **Net Amount in words**_____ **Add GST** _____ **Total Amount (Including GST)** _____ **Total Amount in words** _____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within Seven (7) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 6 months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-II) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,