UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 30.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below

is scheduled to be held on 06 **.11.2025 at 12.00 PM** in the Office **of the University**

Works

Department. Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 06.11.2025 upto 12.00 PM

Opening of Quotations:- 06.11.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: "Replacement of CPVC water lines at 1st floor centre wing F Hostel" in UoH campus	Rs. 37,072.74/-

Sd/-

Executive Engineer A/C

Name of work: Maintenance of Building: -"Replacement of CPVC water lines at1 st Floor Center wing F Hostel" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1/a	15.44	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	15.44.1	15 mm to 40 mm nominal bore	74.00	Rmt	Figure: Rs_____ Words: // Rupees_____ _____	
2	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.				
	18.7.3	25 mm nominal outer dia Pipes	23.5	RMt	Figure: Rs_____ Words: // Rupees_____ _____	
3	18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
	18.13.1	25 to 40 mm nominal bore	5.00	Each	Figure: Rs_____ Words: // Rupees_____ _____	

4	18.76	Cutting holes up to 30x30 cm in walls including making good the same:				
	18.76.1	With common burnt clay F.P.S. (non modular) bricks	9.00	Each	Figure: Rs_____ Words: // Rupees_____ _____	
5	18.51	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms				
	18.51.1	15 mm nominal bore	5.00	Each	Figure: Rs_____ Words: // Rupees_____ _____	
6	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
	18.53.1	15 mm nominal bore	8.00	Each	Figure: Rs_____ Words: // Rupees_____ _____	
7	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :				
	18.21.2.1	15 mm nominal bore	8.00	Each	Figure: Rs_____ Words: // Rupees_____ _____	
					Total Amount	
		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words**_____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,