UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/

Date: 22.07.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **22.07.2025 at 12.00 P.M. in the Office of the University Works Department.**
Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 22.07.2025 at 12.00 PM
Opening of Quotations: 22.07.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
	Name of work :- Maintenance of Buildings- "Providing mesh doors and other minor repair works in TF-28 Quarter" in UoH Campus.	**RS.49,900/-**

EXECUTIVE ENGINEER A/C

Name of work :- Maintenance of Buildings- "Providing mesh doors and other minor repair works in TF-28 Quarter" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount	
1	1/15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.					
	15.23.1	For thickness of tiles 10 mm to 25 mm	6.00	Sqm	Figure: Rs_____		Wo
2	2/15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	0.30	Cum	Figure: Rs_____		Wo
3	3/11.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	6.00	Sqm	Figure: Rs_____		Wo

4	4/13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :	31.80	Sqm			
	13.61.1	Two or more coats on new work.			Figure: Rs_____		Wo
5	5/14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :	9.20	Sqm	Figure: Rs_____		Wo
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)					
6	6/13.81	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade.	9.20	Sqm	Figure: Rs_____		Wo
	13.81.1	Old work (one or more coats)					
7	7/14.28	Providing and fixing brass curtain rods of wall thickness 1.25mm with two brass brackets fixed with brass screws and wooden plugs etc. wherever necessary complete.	7.20	Rmt	Figure: Rs_____		Wo
	14.28.1	20 mm diameter.					
8	8/9.83	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door	1.00	Each	Figure: Rs_____		Wo

		width upto 700 mm), with necessary accessories and screws etc. complete.				
9	9/9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.06	Cum	Figure: Rs_____	Wo
	9.1.1	Second class teak wood				
	10/MR	Supply and fixing of SS mesh door using with heavy thick powder coated aluminium sections for framing, stainless steel mesh with 304 grade (Jindal make) and it is inlcusive of necessary hardware like magnets, hinges, handles, rubber beading , screws, etc. if any necessary directed by Engineer-in-Charge. **Make: JINDAL (Door size : 0.90 x 2.10 m)**	3.00	Each	Figure: Rs_____	Wo
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **ExecutiveEngineer**

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 ½ % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 1 (One) year from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,