UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 29.05.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **02.06.2025 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 02.06.2025 at 12.00 PM

Opening of Quotations: 02.06.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Repairs and replacement of Ball Bearing, rewinding for 48”&56” Ceiling fans for Zakir Hussain, Lecture Hall complex-II (SRK) Teaching& Non-teaching staff quarters in UoH campus- Reg.	**RS. 36,886/-**

Assistant Engineer

Name of Work: - Repairs and replacement of Ball Bearing, rewinding for 48"&56" Ceiling fans for Zakir Hussain, Lecture Hall complex-II (SRK) Teaching& Non-teaching staff quarters in UoH campus- Reg.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	DSR/MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	MR	Removal of Existing Bearing from 48"/56" ceiling fans and replacements of 6201/6202 (Top and Bottom) Bearing and Labour charges	56 No's	Each	Figure:Rs_____ Words:Rupees_____ _____	
2	MR	Rewinding of "48"/56" ceiling fans with 35/36 SWG copper wire including, labour charges and transportation etc.,as required.	60 No's	Each	Figure:Rs_____ Words:Rupees_____ _____	
3	MR	Supply and fixing of oil condenser Tibcon Make.2.5 MFD	60 No's	Each	Figure:Rs_____ Words:Rupees_____ _____	
		Sub Total				
		GST @ 18%				
		Total				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state
   or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.
2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the Value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of Defects pointed out to him during the execution of the work/Defect Liability Period.
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,