UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 11.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **14.11.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 14.11.2025 upto 12.00PM

Opening of Quotations:- 14.11.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Repair and renovation toilets at student union office" in UoH campus	Rs. 49,950/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenanace of Buildings- "Repair and renovation toilets at Student Union office " in UoH Campus.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	0.80	Cum	Rs_____ Rupees_____ _____	
	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)				
2	15.52	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	2.00	Each	Rs_____ Rupees_____ _____	
3	15.45	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes & lead at site within 50 metre lead as per direction of Engineer-in-charge:	9.60	Rmt	Rs_____ Rupees_____ _____	
	15.45.1	Up to 150 mm diameter				
4	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials	0.80	Cum	Rs_____ Rupees_____	

		by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.			_____	
5	4.1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :	0.65	Cum	Rs_____ Rupees_____ _____	
	4.1.8	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).				
6	11.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	5.40	Sqm	Rs_____ Rupees_____ _____	
7	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and				

		making good the walls and floors wherever required:	1.00	Each	Rs_____ Rupees_____ _____	
	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests				
8	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :	1.00	Each	Rs_____ Rupees_____ _____	
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid				
9	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall	9.60	Rmt	Rs_____ Rupees_____ _____	
	18.7.3	25 mm nominal outer dia. Pipes.				
10	MR	Providing and fixing at all floors Type B - SWR PVC pipes including all fittings such as plain and door bends, tees, elbows, equal and unequal junctions, heel rest sanitary bends, collars etc.(except floor traps/P traps) confirming to IS13592, IS 14735, including jointing with solvent and providing necessary supports, clamps/MS brackets at specified	6.40	Rmt	Rs_____ Rupees_____ _____	

		intervals. The joints of pipe and fittings shall be of drip seal jointing in exposed areas like in shafts etc. and pasted type (solvent) for all other locations all complete and as per directions of Engineer - in - charge.MS brackets shall be paid separately. 110 mm diameter				
11	MR	Providing and fixing at all floors Type B - SWR PVC pipes including all fittings such as plain and door bends, tees, elbows, equal and unequal junctions, heel rest sanitary bends, collars etc. (except floor traps/P traps) confirming to IS13592, IS 14735, including jointing with solvent and providing necessary supports, clamps/MS brackets at specified intervals. The joints of pipe and fittings shall be of drip seal jointing in exposed areas like in shafts etc. and pasted type (solvent) for all other locations all complete and as per directions of Engineer - in - charge.MS brackets shall be paid separately. 75 mm diameter	9.60	Rmt	Rs_____ Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor	**sd/-** **ExecutiveEngineer**

Terms & Conditions:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,