UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 18.02.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **23.02.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 23.02.2026 up to 12.00 PM

Opening of Quotations - 23.02.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings'' Replacement of drain line & construction of man hole near TG-05 at MH-A." in UoH campus	Rs. 25,526.70. /-

Sd/-
Executive Engineer

Name of work: Maintenance of Building: - "Replacement of Drain line & Construction of Man hole near TG-05 at MH-A ." in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.** **3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.** **4) The HSN Code for each item should be indicated.**						
SCHEDULE OF QUANTITIES						
S.No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	2.10.1.2	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	10	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
2	19.6.4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 300 mm dia. R.C.C. pipe	10	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
3	19.7.1.1	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat	1	Each	Figure: Rs_____ Words: Rupees_____ _____	

		cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount (excluding GST)**_____ **Net Amount in words**_____ **Add GST** _____ **Total Amount (Including GST)** _____ **Total Amount in words** _____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,