UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 06.02.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **10.02.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 10.02.2026 up to 12.00 PM

Opening of Quotations - 10.02.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings'' Replacement of EWC in washroom at C-10 and replacement of flush door at C-28, C-32 & D-12 Qtrs.'' in UoH campus	Rs. 39,832 /-

Sd/-
Executive Engineer

Name of work: Maintenance of Building: - "Replacement of EWC in washroom at C-10 and replacement of flush doors at C-28 , C-32 & D-12 quarters." in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

SCHEDULE OF QUANTITIES

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.23.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	1.80	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
2	15.2.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or lenear mix (i/c equivalent design mix)	0.18	Cum	Figure: Rs_____ Words: Rupees_____ _____	
3	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm(thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement :4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc.,., complete.	1.80	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

4	4.1.10A	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 manufactured sands derived from Recycled Concrete Aggregate (RCA) : 10 graded stone aggregate 40 mm nominal size including Recycled Aggregate (RA))	0.18	Cum	Figure: Rs_____ Words: Rupees_____ _____	
5	17.2.1	P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
6	17.28.2.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	2	Each	Figure: Rs_____ Words: Rupees_____ _____	
7	19.60.1.2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 100 mm outlet Sand Cast Iron S&S as per IS- 1729.	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
8	18.21.1.2	Providing and fixing uplasticised PVC connection pipe with brass unions : 30 cm length 20 mm nominal bore	2	Each	Figure: Rs_____ Words: Rupees_____ _____	
9	12.41.1	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameter	2	Rmt	Figure: Rs_____ Words: Rupees_____ _____	

	12.41.2	100 mm diameter	2	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
10	12.42.3.1	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 75x75x75 mm	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.3.2	110x110x110 mm	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.4.1	Single tee without door 75x75x75 mm	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.4.2	110x110x110 mm	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.5.1	Bend 87.5° 75 mm bend	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.5.2	110 mm bend	1	Each	Figure: Rs_____ Words: Rupees_____ _____	

11	15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	5	Each	Figure: Rs_____ Words: Rupees_____ _____	
12	9.21.2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	5	Each	Figure: Rs_____ Words: Rupees_____ _____	
13	9.96.1	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :	5	Each	Figure: Rs_____ Words: Rupees_____ _____	
14	9.97.4	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	5	Each	Figure: Rs_____ Words: Rupees_____ _____	
15	9.100.1	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	10	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	

		Less Rebate Offered if any_____ **Net Amount (excluding GST)**_____ **Net Amount in words**_____ **Add GST** _____ **Total Amount (Including GST)** _____ **Total Amount in words** _____

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,