UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 04.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **07.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 07.08.2025 upto 12.00 PM

Opening of Quotations:- 07.08.2025 at 12.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Minor repairs in Kitchen at G & F Hostel in UoH campus	Rs. 32,488/-

Sd/-
Executive Engineer A/C

Name of work :- Maintenance of Buildings - " Minor Repairs in kitchen at G & F Hostel " in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	1/2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.			Figure: Rs_____ Words: Rupees_____ _____	
	2.8.1	All kinds of soil.	0.81	cum		
2	2/4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :			Figure: Rs_____ Words: Rupees_____ _____	
	a) 4.1.8	1:2:4 (1 cement : 4 coarse sand(zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	1.05	cum		
	b) 4.1.3	1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.72	cum	Figure: Rs_____ Words: Rupees_____ _____	
3	3/6.12	Half brick masonry with common burnt clay F.P.S. (non modular) bricksof class designation 7.5 in foundations and plinth in	2.40	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	6.12.2	Cement mortar 1:4 (1 cement :4 coarse sand)				

4	4/13.8	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix :	14.70	sqm	Figure: Rs_____ Words: Rupees_____	
	13.8.1	1:3 (1 cement: 3 fine sand)				
5	5/9.21	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters :	2.21	sqm	Figure: Rs_____ Words: Rupees_____ _____	
	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.				
6	6/9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :	1.00	each	Figure: Rs_____ Words: Rupees_____ _____	
	9.96.1	300x16 mm				
7	7/9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	2.00	each	Figure: Rs_____ Words: Rupees_____	
	9.97.4	150x10 mm				
8	8/9.100	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete	2.00	each	Figure: Rs_____ Words: Rupees_____	

	9.100.1	125 mm				
9	9/13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	5.30	sqm	Figure: Rs_____ Words: Rupees_____	
	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture				
10	10/10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.	25.00	kg	Figure: Rs_____ Words: Rupees_____	
	10.25.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

Signature of the Contractor

Sd/-
Executive Engineer A/C

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period Six (06) Months from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-II)
2. Office Copy