UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ Date: 05.06.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **12.06.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following Details.

Submission of Quotations - 12.06.2026 up to 12.00 PM

Opening of Quotations - 12.06.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Building'' Replacement flush doors and Cupboard Shutters at D-37 Qtrs." in UoH campus	Rs. 32,830/-

Sd/-
Executive Engineer

Name of work :- Maintenanace of Buildings- "Replacement flush doors and Cupboard Shutters at D-37 Qtr " in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	3.00	Each	Rs_____ Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below				
2	9.21	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters :	3.78	Sqm	Rs_____ Rupees_____ _____	
	9.21.1	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.				
3	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :	2.00	Each	Rs_____ Rupees_____ _____	

	9.96.1	300x16 mm				
4	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	10.00	Each	Rs_____ Rupees_____ _____	
	9.97.4	150x10 mm				
5	9.100	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	10.00	Each	Rs_____ Rupees_____ _____	
	9.100.1	125 mm				
6	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	9.07	Sqm	Rs_____ Rupees_____ _____	
	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture				
7	9.129	Providing and fixing cup board shutters 25mm thick, with Pre-laminated flat pressed three layer particle board or graded wood particle board IS: 12823 marked exterior grade (Grade I Type II) having one side decorative lamination and other side balancing lamination including IInd class teak wood lipping of 25mm wide x12 mm thick with necessary screws and bright finished stainless steel piano hinges complete as per direction of the Engineer-in-Charge	7.56	Sqm	Rs_____ Rupees_____ _____	

8	10.13	Providing and fixing T-iron frames for doors, windows and ventilators of mild steel Tee-sections, joints mitred and welded, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.	20.00	Kg	Rs_____ Rupees_____ _____	
	10.13.1	Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____1_____ **_____** **in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within Seven (07) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,