UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 19.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **26.08.2025 at 3.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 26.08.2025 upto 03.00 PM

Opening of Quotations:- 26.08.2025 at 03.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: "Replacement of the toilet seat in the Gents Toilet, First floor, near Room C-250, (FF,L-02) at School of Medical Sciences" in UoH Campus.	Rs. 14,197/-

Sd/-
Executive Engineer A/C

Name of work: - Maintenance of Buildings "Replacement of the toilet seat in the Gents Toilet, First floor , near Room C-250, (FF,L-02) at School of Medical Sciences" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.			Rs_____ Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm	2.25	Sqm		
2	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	0.23	Cum	Rs_____ Rupees_____ _____	
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	0.23	Cum	Rs_____ Rupees_____ _____	
	4.1.3	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)				
4	11.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	2.25	Sqm	Rs_____ Rupees_____ _____	
5	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle	1.00	Each	Rs_____ Rupees_____ _____	

		lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid				
6	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931	1.00	Each	Rs_____ Rupees_____ _____	
	18.53.1	15mm nominal bore				
7	18.58	Providing and fixing PTMT grating of approved quality and colour.	1.00	Each	Rs_____ Rupees_____ _____	
	18.58.1	Circular type.				
	18.58.1.2	125 mm nominal dia with 25 mm waste hole.				
8	MR	Supply and fixing of C.P. Two in One tap of 15 mm dia. (Make: Jaquer / Seiko)	1.00	Each	Rs_____ Rupees_____ _____	
9	MR	Supply and fixing of C.P. Health Faucet of 15 mm dia. (Make: Jaquer / Plumber)	1.00	Each	Rs_____ Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				

Signature of the Contractor

Sd/-
Executive Engineer A/C

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
5. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
6. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
7. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
8. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
9. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy