UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 04-06-2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **09.06.2025 at 12.00 P.M. in the Office of the University Works Department.**

Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 09.06.2025 at 12.00 PM

Opening of Quotations: 09.06.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	**Name of work: Maintenance of Building: - Replacement of floor tiles in meeting room at health centre" in UoH Campus.**	**RS. 36,700/-**

Name of work: Maintenance of Building: - Replacement of floor tiles in meeting room at health centre" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.	17.05	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm				
2	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	0.85	Cum	Figure: Rs_____ Words: Rupees_____ _____	
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :			Figure: Rs_____ Words: Rupees_____ _____	
	4.1.3	1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.75	Cum		
4	11.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm(thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades,	17.05	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

		except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer A/c.**

Terms & Conditions:

1. The work should be completed within thirty (30) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period Six (06) Months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST (18%) will be levied wherever applicable.

Executive Engineer A/C.

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,