UNIVERSITY OF HYDERABAD
{Establishment by the act of the Parliament in 1974}
Gachibowli, Hyderabad
University Works Department,
Ph no.040-23132306/040-23101208
E-mail: aet.uohyd@gmail.com

E-QUOTATION

FOR

NOTICE INVITING QUOTATION (NIQ)

Notice Inviting e-Tender No. & Date	**UH/ENGG/UWD/2025-26/13**
Name of the work	**Name of work:- 1st Recall-Replacement of spares for Power Capacitor panels at various electrical sub-stations" in the University of Hyderabad Campus.**
Estimated Cost	**Rs. 2,18,648/- (Inclusive of GST)**
Earnest Money Deposit (EMD)	**EMD @ 2% of the estimated cost i.e., Rs. 4,373/- (DD or Bank Guarantee)**
Time Allowed	**01 Month**
Date of start of Bid Submission	**13.01.2026, 2.30 PM**
Last date & Time for Submission of Bids	**21.01.2026, 3.00 PM**
Date & Time of Opening of Technical Bids	**22.01.2026, 3.00 PM**
Date & Time of Opening of Financial Bids	**Will be intimated to technically qualified bidders in due course of time through Central Public Procurement portal.**
Submission of hard copies of EMD	The original EMD should be submitted in the University Works Department, University of Hyderabad, Gachibowli, P.O. Central University, HYDERABAD – 500046 up to 3.00 PM on 22.01.2026.

Sd/-
ASSISTANT ENGINEER (E)

Sd/-
UNIVERSITY ENGINEER

General Conditions & Eligibility Criteria for Submission of Quotation:-

1. The contractor/bidder shall be a registered contractor under appropriate class and should produce definite proof of registration by state or central government departments or state/central autonomous bodies or undertakings.

2. The bidder should also submit self-attested copies of relevant IT returns, PAN no, valid Registration Certificate and Experience certificate having successfully completed Civil works of required value and shall sign all the pages of Technical & price bid without fail.

3. The bidders except Micro and Small Medium Enterprises (MSEs) notified under MSME, Procurement Policy (as per Rule 170 of GFR 2017), should pay EMD of 2% of Estimated Cost drawn in favor of "Finance Officer, University of Hyderabad" payable at Hyderabad.

4. Statutory taxes/Deductions shall be made as per rules.

5. The Competent Authority on behalf of the University of Hyderabad does not bind itself to accept the lowest or any other quotation and reserves to itself to reject any or all the quotations received without assigning any reason. All quotations in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.

6. Work to be carried out in the presence and under supervision of UWD Engineers.

7. The site shall be made available as and when required for execution of work.

8. Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the quotations submitted by the contractors who resort to canvassing will be liable for rejection.

9. The Contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's compensation Act.

10 The Work Order can be cancelled and the work can be stopped at any time by the Engineer-in-charge of the work or by any officer superior to him in authority.

11 The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

12 If water is supplied by the University, 1 % of the actual cost of water consuming items will be recovered from work bills.

13 Seigniorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

14 The contractor shall permit the University to **deduct 10% of the value of each work bill towards Security Deposits** shall be released after expire of defects liability period. The deposit is liable to be forfeited to the University for Non-rectification of defects pointed out to him during execution of work/Defect Liability Period.

Signature of the Contractor

15 Defect liability period of **6 Month** commences from the date of satisfactory completion of work.

16 For delay or slow progress of work, relevant clauses of CPWD manual will be invoked and penalty levied. If work is delayed, the University reserves the right to foreclose / rescind the work, without risk and cost and to get the balance work done through any other contractor, and the contractor shall have no right to claim any compensation on this account.

17 In case, the work cannot be started due to reasons not within the control of the contractor within $1/8^{th}$ of the stipulated time for completion of work, either party may close the contract. In such eventuality, the Earnest Money Deposit of the contractor shall be refunded, but no payment on account of interest, loss of profit or damages etc. shall be payable at all.

18 The Contractor should ensure while executing the work that there should be no deviation / variation beyond permissible limit.

19 The work of each item is to be executed in consultation with the user Department.

20 In case of execution of any extra items / additions, alterations / changes, the total amount may not exceed sanctioned amount; if it exceeds, prior approval is be taken from the User Department and Competent Authority.

21 Assistant Engineer (Civil)/Assistant Engineer (Electrical) has to enclose the work completion certificate and **No claim certificate** from the contractor to the final bill.

22 Certificate of satisfactory completion of work from user department and or Engineer in charge may be obtained and enclosed to the final bill for payment.

23 Further details can be had from the Office of the University Engineer, University of Hyderabad, Hyderabad-5000 046 during working hours.

24 GST invoice form should be filled and submitted along with the bill.

25 Labour engaged and working equipment brought to site by the contractor shall be recorded in the UoH Security main gate and necessary gate pass obtained before entering in to the premises.

Signature of the Contractor

LIST SHOWING PREFERRED BRANDS/MANUFACTURERS/MAKE

NOTE: - 1) A List of Preferred Brand Names of Various Materials / Products are shown below for usage in execution of Work. However, Approved equivalent material of any other Specialized Companies / Firms may also be used , in case it is established that the Brands Specified below are not available in the market and subject to Approval of the alternate Brand by the Engineer In charge.

2) It must be ensured, in general, that all materials to be used in the works shall bear BIS Certification mark. In cases where for a particular material/product, BIS Certification Mark is not available, then the material proposed to be procured can be used subject to the condition that it should conform to CPWD Specifications and relevant BIS codes. In such cases written approval of the Engineer-in -Charge shall be obtained before use of such material in their works.

3) The list given below does not absolve the Executing Agency from their responsibility for using these products. It is only after, they are satisfied about the quality and performance, the products shall be used. To achieve this, proper check on the quality of the product, actually to be used, should be exercised.

S.No	Product	Make
1	Ordinary Portland Cement	ACC, Ultratech, Vikram, Shree Cement, Ambuja, Jaypee Cement, Century Cement, JK Cement, Penna Cement , Bharathi Cement, Maha , Nagarjuna and Brands Approved by CE(SZ)II,CPWD,Hyderabad.
2	Portland Pozzolana Cement	
3	White Cement	Birla, J.K. White, Travancore
4	Reinforcement steel – (Primary Producers)	RINL, SAIL, TATA STEEL Ltd., JSW STEEL Ltd., JINDAL STEEL & POWER Ltd., Shyam produced by M/s.Shyam Steel Industries Ltd and Manufacturers approved by Spl.DG(SR),CPWD,Chennai
5	Ready Mix Concrete (RMC)	Ultra Tech, ACC, RMC Ready Mix (India), Nuvoco Vistas Corporation Ltd., (formally known as Lafarge India Ltd.), RMC by M/s Aparna Enterprises limited,Hyderabad, RDC Concrete (India) Pvt. Ltd and additional firms approved by CE, SZ-II, CPWD, Hyderabad.
6	Pulverized Stone Sand/ Crushed Stone Sand (Manufactured Sand)	Rank Enterprises, Robo Sand.
7	Polymer based Curing Compounds	FOSROC, SIKA, BASF
8	Structural Steel Sections	TATA, SAIL,RINL, JINDAL Steel & Power Ltd., J SW
9	Hollow Steel Tube Sections	TATA, Jindal, Apollo
10	Fly ash Cement Bricks	KSP Industries, Prakash International Ltd, NUBRIC.

Signature of the Contractor

11	Autoclaved Aerated Concrete Blocks (AAC)	M/s. Hyderabad Industries Ltd., M/s. Ultra Tech India Limited, M/s. Siporex India Ltd., NCL, NUBRIC.
12	Binding Wire	TATA, JSW
13	Factory Made Cement Concrete Cover Blocks	A.S.R. Cover Blocks, Stand alone Universal Concrete Cover Blocks
14	RCC Door Frames	Ventura, Bothra.
15	Flush Door Shutters	Raavela Doors, Indian Timber Products, Kitply,
16	Fire Check / Rated Doors	Navair, Godrej, Shaktimet, Kenwood, MPP Schodders.
17	Smoke Seal Strip	Promat, Astro flame
18	Plain / Prelaminated Particle Board	ECO Board, TESA Action Co., Kitlam, Archid ply, Century
19	Ply wood / Laminate	Kitply, Centuryply, Greenply, Merino, Sonear (Donear), Formica, Archidply, Royal touch .
20	Natural wood Veneers	Kitply, Centuryply, Sonear (Donear), Greenply Archidply, Durain, National Action Tesa, Anchor.
21	Adhesive / Glue	Pidilite, Dunlope, Sika, Fosroc, Vamorganic.
22	Steel Windows/ Pressed Steel Frames	Madhu Industries, (Bengaluru), San Harvic, NCL
23	Cement Bonded Particle Board	BISON Boards of NCL.
24	PVC Door Frames & Shutters	Rajshri Plastiwood, Sintex.
25	FRP Door Frames & Shutters	Meena Fibre Glass, Duroplast, Cactus, Polyline.
26	UPVC Windows	Fenesta, Kommerling , Rehau, Wintech, LG, Encraft – Madhu Industries, Polywood.
27	Ceramic Floor /Dado Tiles	Somany, Johnson, Kajaria, Orient, Bell, RAK, Asian, NITCO, AGL tiles.
28	Vitrified Tiles	Somany, Johnson, Kajaria, Orient Bell Ltd, RAK, Vitero brand Aparna tiles
29	Precast Terrazo Tiles	NITCO, Hindustan, Modern
30	Precast Chequered Tiles	NITCO, Hindustan, INDO, Bharat, Poddar.
31	Non Metallic Floor Surface Hardners	Ironite, Hardonite, FOSROC, SIKA, BASF, CICO, Pidilite.
32	Precast Cement Concrete Tiles	NITCO, Hindustan, INDO, Ultra, NTC, Poddar.
33	Factory made Cement Concrete Interlocking Paver Blocks	Earth Pavers Hyd. Pvt. Ltd., NITCO (Rockard), Bharat (Nilsan), Classic Tiles.
34	Grass Paver	Unistone, Ultra.
35	Glass Mosaic Tiles	Palladio, Coral, Mridul, Bisazza

Signature of the Contractor

36	PVC Flooring	LG Hausys, Ger Flor, Armstrong .
37	High Density Fibre (HDF) Pre-laminated Flooring boards	Pergo, Armstrong.
38	Unglazed Heavy Duty Vitrified Tiles	Somany (Dura Gres), Kajaria (Pavigres).
39	Unglazed Heavy Duty Paver/Parking Tiles	Somany (Dura Stone), Johnson (Endura),
40	Clay Tiles on Roof	Kenjai, Johnson, Common Wealth Trust (Ind) Ltd
41	Tile Adhesives	Laticrete, ,Ardex Endura, Weber, Roff. SIKA, Ferrous.
42	Grout Compound/ Epoxy Grouts	Laticrete, Ardex Endura, Weber, Fosroc, Pidilite, SIKA, Ferrous, BASF, CICO.
43	Epoxy Motor	Fosroc, SIKA, BASF
44	Water Proofing Compound	Fosroc, CICO, SIKA, Pidilite, , BASF, Accoproof, Ardex Endura.
45	Damp Proof Material	Duraseal, Acco-proof, Impermo
46	Actactic Polypropylene (APP) Modified Water Proof Membrane	S T P, Bitumat Co. Ltd., Pidilite, Hydrotech Ltd.
47	Admixtures / Platisizers	Fosroc, CICO, SIKA, BASF, MC
48	Ethylene Propylene Diene Monomer (EPDM) Gasket	Hanu /Anand
49	Aluminium Extruded sections	Jindal, Hindalco, Indian Aluminium Co.
50	Polyester Powder Coating	Nerolac, Berger, Akzonobel, Jotun
51	Poly Sulphide Sealant	Pidilite, Tuffseal, Choksey chemicals.
52	Cement Based Wall putty	Birla Wall Care, J.K. Wall putty, Berger Paints , Asian Paints.
53	Paints/ Primer / Acrylic Emulsion (Premium Quality)	ICI Dulux, Asian Paints, Berger, Nerolac .
54	Melamine Polish	Asian Paints, Melamyne Gold Wudfin of Pidilite Industries, Timbertone of ICI Dulux.
55	Water Proofing Cement Paint	Snowcem India, ICI Dulux, Berger, Asian.
56	PU Enamel Metallic Paints on MS Structure & Epoxy paints (Premium Quality)	SKK, Akzonobel, Asian, Berger, MRF.
57	Calcium Silicate False Ceiling Tiles	Aerolite Co, Hilux, Armstrong
58	Gypsum Board False Ceiling Tiles	Saint Gobain, Lafarge, Amstrong Co.
59	Mineral Fibre Board False Ceiling Tiles	Armstrong , Decosonic.
60	Rockwool / Glasswool insulation.	Twigafiber, Llyod Insulation, Supreme.
61	False Flooring System .	Kebao, Pinnacle, Access Floor System
62	Anodised / Powder Coated Aluminium Fittings / Fixtures-	Everite, Jyoti, Shakti, Sigma (BIS mark), Hardima.
63	Stainless Steel Pipes (Railing)	Jindal Stainless Steel Ltd., Connect Architectural Products Pvt. Ltd.

Signature of the Contractor

64	Stainless Steel Wire Mesh	Champion Make, GKD.
65	Float / Plain / Tinted / Tempered / Toughened Glass.	Modi, Saint Gobain, Asahi, Atul, Glaverbel, Pilkington .
66	Mirror Glass.	Modi Guard, Atul, Asahi, Goldenfish.
67	Hydraulic Door Closers / Floor Springs	Godrej, Hardwyn, Everite, Dorma, Dorset, Magnum, Kich.
68	Steel Nuts, Bolts and Screws-	Atul, Hilti, Kundan, Priya .
69	Ball Bearing Hinges and Spring Hinges	Dorma, Hafele, Geze, Dorset, Magnum.
70	Stainless Steel Screws	Kundan, Arrow, Nettlefold, GKW.
71	Clamping System Using Dash / Anchor Fastners.	Hilti, Fischer,Bosch, Canon.
72	Locks in Furniture Cabinets.	Hettich, Blum, Hafel, Godrej, Link, Harrison.
73	Four Point / Multi Point Locking Handle.	Hefele, Alu-Alfa, Geze, Dorma, Godrej .
74	Stainless Steel Friction stay hinges	Hafele, Earl Bihari
75	Door closer lock / Panic exit device	Ingersoll Rand, Dorma, Monarch.
76	Door Coordinator	UL Listed, Monarch.
77	Precoated Galvolume Iron Profile Sheets.	Pennar, TATA Blue scope, NCL.
78	Multi Walled PolyCarbonate Roofing Sheets	Lexan, GE
79	Bitumen	Indian Oil, Hindustan Petroleum Corporation.
80	Aluminium Composite Panels (ACP)	Alstrong, Alucobond, Aluplex, Alubond.
81	Structural Glazing	Modi, Saint Gobain, Asahi, Glaverbel.
82	Structural and Weather Sealants (Silicon)	Dow Corning, Wacker., GE, BASF
83	Adhesive Tape	Norton
84	Spider Patch Fittings for Structural Glazing	Dorma, Sevax, Kich, Ozone, Hafele.
85	G.I. Pipes -	TATA, Jindal, Zenith, Hissar .
86	G.I. Fittings	HB, R Brand, Unik, ICS.
87	Gun Metal Valves / Non Return Valves	Zoloto, Leader, Sant.
88	C.I. Sluice Valves (Double Flanged)	Zoloto, Leader, SANT, Kirloskar, IVC, Burn.
89	PTMT fittings/ fixtures	Prayag, Shakti, pearl.
90	C.P. Brass fittings/ fixtures	Jaquar , Marc, Plumber, ESS ESS, TOTO, Parko, Nova , Grohe.
91	C.P.V.C pipes & specials	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex, Flowguard.
92	uPVC Pipes & Fittings.	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex.
93	Poly Propylene Random Co polymer (PPR) Pipes & Specials	SFMC, Victus, Supreme , Prince.

Signature of the Contractor

94	Centrifugally Cast (spun) Pipes & Fittings (Sanitary Pipes)/ Centrifugally Cast iron hub less pipes	NECO , HEPCO, SKF, Bengal Iron Corporation (BIC) / NECO, kepsilan
95	Centrifugally Cast (spun) Pipes (LA) & Fittings (Water Supply Pipes) /	Electro steel, Kesoram, LANCO Industries, RIF, NECO./ NECO, kepsilan
96	Vitreous China Sanitary ware	Parryware, Neycer, Hindware, Cera, Jaquar, TOTO, Duravit.
97	Stainless Steel Sinks	Nirali, Kaff, Hindware, Johnson, Signature, Neelkanth, Cobra, Diamond.
98	Fire Clay Sinks	Sunfire, Parryware, Hindware.
99	Sensor Based Auto Flush Systems	A O S Systems, TOTO, Parryware, Hindware, Grohe, Kochler.
100	PVC Water Storage Tanks	Sintex, Uniplast, Durocon, Polycon, Supreme.
101	Float Valve (Ball Valve)	Prayag, Leader, Zoloto, IBP, Arco.
102	Water Meter	Zoloto, Leader, Dashmesh.
103	RCC Non Pressure (NP-2) Pipes -	Indo., Hindustan, Balaji Pipe Industries, Indian Hume Pipes Ltd.
104	Factory Made SFRC (RCC) Manhole Covers	Indo, Balaji Pipe Industries, Supreme.
105	CI Manhole Covers	SKF, HIF, Neco, Bengal Iron Corporation (BIC).
106	Coupler for reinforcement bars	LOKPAL Industries – Noida, Shree ISPAT Traders – Jaipur, Trimurthi Engg. & Fab Works – Nagpur, National cutting Tools Sai Couplings – Pune, SPROCS Rebar Couplings Kanva Trading – Chennai.
107	L.T. Power Cable	Finolex/ Universal/ Fort Gloster/ Polycab/ Havells
108	Modular switch, socket power	TOYONA (Accura) Anchor (Roma)
	Socket TV Telephone Socket	
109	Modular switch, socket power	TOYONA (Accura) Anchor (Roma)
110	CFL Lamps & Fittings	Havells/Philips/Crompton

Signature of the Contract

Name of work: "1st Recall- Replacement of spares for Power Capacitor panels at various electrical sub-stations" in the University of Hyderabad Campus.									
1) The estimates amount is inclusive of GST. **2) The bidder should quote basic rates exclusive of GST and quote GST percentage separately; GST should be revised from time to time.**									
S.No	**DSR No.**	**Description of items**	**Qty**	**Unit**	**Basic Rate in Figures to be entered by the Bidder without GST**	**Add: GST (%)**	**Total Amount without GST**	**Total Amount with GST**	**Total Amount with GST in words**
1	MR	Supply & fixing of 10 KVAR rating Capacitor Duty Contactors (with 1No +1NC with Add on block) including connections etc as required. Make: L & T/ C&S.	5.00	Each					
2	MR	Supply & fixing of following rating Heavy Duty Capacitors of following Type. Make: L&T / Neptune / Capco.							
2.1		5 KVAR Cylindrical Type	1.00	Each					
2.2		10 KVAR Cylindrical Type	13.00	Each					
2.3		8.5 KVAR Box Type	4.00	Each					
2.4		10 KVAR Box Type	5.00	Each					
2.5		15 KVAR Box Type	1.00	Each					
3	MR	Supply, installation, testing & commissioning of Automatic Power factor Correction (APFC) Relay/Controller of following rating/step including dismantling of old controller from panel etc as required. Make: L & T/ C&S/Neptune.							
3.1		6 STAGES	1.00	Each					
3.2		8 STAGES	2.00	Each					
3.3		12 STAGES	1.00	Each					

4	MR	Supply & fixing of following current transformer of 15VA burden, IS 2705 (1992), class1, on existing bus bar/ cable etc., As required. Make: AE/ Kappa							
4.1		400 / 5A	3.00	Each					
4.2		600 / 5A	3.00	Each					
4.3		800 / 5A	3.00	Each					
5	1.17	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.							
5.1	1.17.11	2 x 2.5 sq. mm	45.00	Mtr					
6	1.21	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.							
6.1	1.21.1	20 mm	30.00	Mtr					
7	2.10	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.							
7.1	2.10.4	Triple pole	2.00	Each					

Signature of the Contractor **Sd/-** **University Engineer** **Sd/-** **Assistant Engineer (E)**