UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 03.03.2026.

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **06.03.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 06.03.2026 at 12.00 PM

Opening of Quotations: 06.03.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Replacement of 2 Nos 1000 litres capacity PVC overhead water tanks for Non-Teaching staff Quarters D-36 & 47 in U.O.H campus Reg.	**Rs.35,802/-**

Assistant Engineer (E)

Name of Work:-Replacement of 2 Nos 1000 litres capacity PVC overhead water tanks for Non Teaching staff Quarters D-36 & 47 in U.O.H campus Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. /MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	14.79	Disconnecting damaged overhead/terrace PVC water storage tank of any size from water supply line and removing from the terrace including shifting at ground level as per direction of Engineer-in- charge.	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
2	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. (1000 ltrs x 2Nos)	2000	Per litre	Figure:Rs_____ Words:Rupees_____ _____	
3		Making connection of G.I./CPVC distribution branch with G.I./CPVC main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
3.1	18.13.1	25 to 40 mm nominal bore	4	Each	Figure:Rs_____ Words:Rupees_____ _____	
4		Dismantling G.I. pipes (external work), manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	14.84	(a) Internal Work- Exposed on wall	10	Mtrs	Figure:Rs_____ Words:Rupees_____ _____	
5		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
5.1	18.7.2	20 mm nominal outer dia. Pipes.	15	Mtrs	Figure:Rs_____ Words:Rupees_____ _____	
5.2	18.7.3	25 mm nominal outer dia .Pipes.	6	Mtrs	Figure:Rs_____ Words:Rupees_____ _____	

6		Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball.				
6.1	18.62.3	25 mm nominal bore, 152 mm long. Weighing not less than 440 gms.	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
7		Supply & fixing of follwing accessories on CPVC pipe of size as required.				
7.1	MR	20mm ball valve	4	Each	Figure:Rs_____ Words:Rupees_____ _____	
7.2	MR	25mm ball valve	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
		Sub Total				
		Add GST @ 18%				
		Total				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.
2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,