Name of Work: - Providing new DB with MCB's at Health centre, North shopping complex & H-Hostel in University of Hyderabad campus-Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1		Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.1	1.17.11	2 x 2.5 sq. mm	10	Mtr	Figure:Rs_____ Words:Rupees_____ _____	
2	1.14	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required			Figure:Rs_____ Words:Rupees_____ _____	
2.1	1.14.1	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	20		Figure:Rs_____ Words:Rupees_____ _____	
3		Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus				
3.1	2.4.1	4 way (4 + 12), Double door	1		Figure:Rs_____ Words:Rupees_____ _____	

3.2	2.4.3	8 way (4 + 24), Double door	2		Figure:Rs_____ Words:Rupees_____ _____	
4	2.1	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.			Figure:Rs_____ Words:Rupees_____ _____	
4.1	2.10.1	Single pole	60	Each	Figure:Rs_____ Words:Rupees_____ _____	
4.2	2.10.5	Triple pole and neutral	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
5	1.27	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.				
5.1	1.27.4	6 Module (200mmX75mm)	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
6	1.24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
6.1	1.24.3	15/16 amp switch	1	Each	Figure:Rs_____ Words:Rupees_____ _____	

6.2	1.24.5	6 pin 15/16 amp socket outlet	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
7	MR	Supplying and fixing 63 A four pole 415 V, MCB in the existing DB complete with connections, testing and commissioning etc. as required,. Make:-Legrand/L&T/Philiphs.	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
8	civil 13.1.2	Providing 12 mm thick cement plaster of mix 1:6 (1 cement : 6 fine sand)	2	sqm	Figure:Rs_____ Words:Rupees_____ _____	
		Sub Total				
		GST @ 18%				
		Total				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1.The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.

4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.

5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.

6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.

8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

9. Defect liability period 6 (six) months from the date of completion of the work.

10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.

11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.

12. No quotation will be accepted without PAN/VAT no.

13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,