UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 05.02.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **09.02.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 09.02.2026 at 12.00 PM

Opening of Quotations: 09.02.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Supply and fixing of 4 core x 16 sqmm UG cable from pump house substation to take-off point Room at University of Hyderabad Campus-Reg.	**Rs.49,722/-**

Assistant Engineer (E)

Name of Work: - Supply and fixing of 4 core x 16 sqmm UG cable from pump house substation to take-off point Room at University of Hyderabad Campus-Reg.

SCHEDULE OF QUANTITIES

S. No	D.S.R. No.	Description of item		Unit	Rate in figures & Rate in words	Amount
1	MR	Supply and laying of 4 core x 16 sqmm XLPE Aluminium Armoured power cable of 1.1 KV grade of following size direct in ground (75cm below ground level)including excavation, protective covering and refilling the trench etc as required, but excluding sand cushioning. Make: Finolex/Polycab/Havells.	124	Mtrs	Figure:Rs_____ Words:Rupees_____ _____	
2	9.1	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV Grade as required.				
2.1	9.1.33	4 x 16 Sqmm (28mm)	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
		Sub Total				
		GST @ 18%				
		Total				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:
1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,