UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 31.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below

is scheduled to be held on **06 .11.2025 at 12.00 PM** in the Office **of the University Works**

Department. Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 06.11.2025 upto 12.00PM

Opening of Quotations:- 06.11.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Providing kitchen platform and kitchen sink at school of chemistry" in UoH campus	Rs. 49,651/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenanace of Buildings- "Providing Kitchen platform and kitchen sink at School of Chemistry" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	6.13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floorV level.	3.30	Sqm	Rs_____ Rupees_____ _____	
	6.13.2	Cement mortar 1:4 (1 cement :4 coarse sand)				
2	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :	7.32	Sqm	Rs_____ Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)				
3	13.111	Finishing walls with Acrylic Smooth exterior paint of required shade :	7.32	Sqm	Rs_____ Rupees_____ _____	
	13.111.1	Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface				

4	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.	5.17	Sqm	Rs_____ Rupees_____ _____	
	8.2.2	Granite stone slab colour black, Cherry/Ruby red				
	8.2.2.2	Area of slab over 0.50 sqm				
5	8.3	Providing edge moulding to 18mm thick marble stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in- Charge.	21.40	Rmt	Rs_____ Rupees_____ _____	
	8.3.2	Granite work.				
6	17.10	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS : 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :	1.00	Each	Rs_____ Rupees_____ _____	
	a)17.10.2	Kitchen sink without drain board				

	17.10.2.1	610x510 mm bowl depth 200 mm				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **_____** **in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
ExecutiveEngineer

Terms & Conditions:

1. The work should be completed within thirty (7) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,