UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 05.01.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **12.01.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 12.01.2026 up to 12.00 PM

Opening of Quotations - 12.01.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings'' Repairs to store room in new sports complex'' in UoH campus	Rs. 45,770/-

Sd/-
Executive Engineer

Name of work: Maintenance of Building: - Repairs to store room in New Sports complex." in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.** **3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.** **4) The HSN Code for each item should be indicated.**						
SCHEDULE OF QUANTITIES						
S.No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	21.66	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
2	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	**1.00**	Cum	Figure: Rs_____ Words: Rupees_____ _____	
3	14.83	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	21.66	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
4	11.4	52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	31.72	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
5	13.82	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and	75.97	Sqm		

		manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two Coats			Figure: Rs_____ Words: Rupees_____ _____	
6	13.85	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	15.20	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
7	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	75.97	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
8	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	9.81	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount (excluding GST)**_____ **Net Amount in words**_____ **Add GST** _____ **Total Amount (Including GST)** _____ **Total Amount in words** _____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST (2%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.