UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 26.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 03**.09.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- _03.09.2025 upto 12.00 PM

Opening of Quotations:- _03.09.2025 at 12.00 PM

S.No	Name of the work	EstimatedCost
1	Maintenance of Buildings-:"Replacement of water lines in T1-04&TG-05 at ladies hostel-III" in UoH Campus.	Rs. 48,392.00/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenance of Buildings - "Replacement of water lines in T.1-04 & TG -05 at Ladies Hostel-III" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	1/15.44	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :	20.00	Rmt	Rs_____ Rupees_____ _____	
	a) 15.44.1	15 mm to 40 mm nominal bore				
2	2/18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge : External work	48.00	Rmt	Rs_____ Rupees_____ _____	
	A/ 18.9.3	25mm nominal outer dia. Pipes.				
	B/ 18.9.5	40 mm nominal outer dia. Pipes.	14.80	Rmt	Rs_____ Rupees_____ _____	
3	3/18.6A	Providing and fixing PPR Unions				
	18.6A.4	PPR Union 40 mm	4.00	EAch	Rs_____ Rupees_____ _____	

4	4/18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :	4.00	EAch	Rs_____ Rupees_____ _____	
	18.18.3	25 mm nominal bore				
5	5/18.76	Cutting holes up to 30x30 cm in walls including making good the same:	12.00	EAch	Rs_____ Rupees_____ _____	
	18.76.1	With common burnt clay F.P.S. (non modular) bricks.				
6	6/18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931	8.00	EAch	Rs_____ Rupees_____ _____	
	18.53.1	15mm nominal bore				
7	7/18.51	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms	4.00	EAch	Rs_____ Rupees_____ _____	
	18.51.1	15 mm nominal bore				
8	8/18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :	4.00	EAch	Rs_____ Rupees_____ _____	
	a) 18.21.2	45 cm length				
	18.21.2.2	20 mm nominal bore				
9	9/18.22	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :	4.00	EAch	Rs_____ Rupees_____ _____	
	18.22.2	cutting holes up to 30x30 cm in walls including making good the same:				
10	10/18.52	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.	4.00	EAch	Rs_____ Rupees_____ _____	
	18.52.1	15mm nominal bore				

11	11/17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.	4.00	EAch	Rs_____ Rupees_____ _____	
	a) 17.28.2	Flexible pipe				
	17.28.2.1	32 mm dia				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **_____** **in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within Seven (7) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 6 months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-II) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,