**UNIVERSITY OF HYDERABAD**
**{Establishment by the act of the Parliament in 1974}**
**Gachibowli, Hyderabad**
**University Works Department,**
**Ph no.040-23132306/040-23101208**
**E-mail: aet.uohyd@gmail.com**

## E-QUOTATION

## FOR

## NOTICE INVITING QUOTATION (NIQ)

| | |
|---|---|
| **Notice Inviting e-Tender No. & Date** | **UH/ENGG/UWD/2026-27/04** |
| **Name of the work** | **Name of work:- "Providing Internal Electrification to the Lab in CIS building in University of Hyderabad campus".** |
| **Estimated Cost** | **Rs.4,54,467/- (Inclusive of GST)** |
| **Earnest Money Deposit (EMD)** | **EMD @ 2% of the estimated cost i.e., Rs 9089/- (DD or Bank Guarantee)** |
| **Time Allowed** | **15 days** |
| **Date of start of Bid Submission** | **21.05.2026, 2.30 PM** |
| **Last date & Time for Submission of Bids** | **01.06.2026, 3.00 PM** |
| **Date & Time of Opening of Technical Bids** | **02.06.2026, 3.00 PM** |
| **Date & Time of Opening of Financial Bids** | **Will be intimated to technically qualified bidders in due course of time through Central Public Procurement portal.** |
| **Submission of hard copies of EMD** | The original EMD should be submitted in the University Works Department, University of Hyderabad, Gachibowli, P.O. Central University, HYDERABAD – 500046 upto 3.00 PM on 02.06.2026. |

Sd/-
**ASSISTANT ENGINEER (E)**

**Sd/-**
**UNIVERSITY ENGINEER**

**General Conditions & Eligibility Criteria for Submission of Quotation:-**

1. The contractor/bidder shall be a registered one under appropriate class and should produce definite proof of registration with State or Central Government Departments or State/Central Autonomous Bodies or Undertakings / Shall be registered with MSME under appropriate category.

**2.** The bidder should also submit self-attested copies of relevant IT returns, PAN no, valid Registration Certificate and Experience certificate having successfully completed Civil works of required value and shall sign all the pages of Technical & price bid without fail.

**3.** The bidders except Micro and Small Medium Enterprises (MSEs) notified under MSME, Procurement Policy (as per Rule 170 of GFR 2017), should pay EMD of 2% of Estimated Cost drawn in favor of "Finance Officer, University of Hyderabad" payable at Hyderabad.

4. Statutory taxes/Deductions shall be made as per rules.

5. The Competent Authority on behalf of the University of Hyderabad does not bind itself to accept the lowest or any other quotations and reserves to itself the right to reject any or all the quotations received without assigning any reason. All quotations in which any of the prescribed condition is not fulfilled or any condition including those related to conditional rebate put forth by the tenderer shall be summarily rejected

6. Work to be carried out in the presence and under supervision of UWD Engineers.

7. The site will be made available as and when required for execution of work.

8. Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the quotations submitted by the contractors who resort to canvassing will be liable for rejection.

9. The Contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's compensation Act.

10. The Work Order can be cancelled and the work can be stopped at any time by the Engineer-in-charge of the work or by any officer superior to him in authority.

11. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

12. If water is supplied by the University, 1% of the actual cost of water consuming items will be recovered from work bills.

13. Seigniorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

**Signature of the Contractor**

14. EMD Deposited by the bidders will be refunded to the respected bidders after completion of tendering process

15. The contractor shall permit the University to **deduct 5% of the value of each work bill towards Security Deposit** inaddition to performance guaranty which shall be released after expiry of defects liability period. The deposit is liable to be forfeited to the University for Non-rectification of defects pointed out to him during execution of work/Defect Liability Period.

16. Defect liability period of **(06) Month's** commences from the date of satisfactory completion of work.

17. For delay or slow progress of work, relevant clauses of CPWD manual will be invoked and penalty Will be levied. If work is delayed, the University reserves the right to foreclose / rescind the work, and to get the balance work done through any other contractor, at his risk and cost and the Contractor shall have no right to claim any compensation on this account.

18. In case, the work cannot be started due to reasons not within the control of the contractor within $1/8^{th}$ of the stipulated time for completion of work, either party may close the contract. In such eventuality, the Earnest Money Deposit of the contractor shall be refunded, but no payment on account of interest, loss of profit or damages etc. shall be payable.

19. The Contractor should ensure while executing the work that there should be no deviation / variation beyond permissible limit.

20. The work of each item is to be executed in consultation with the user Department.

21. In case of execution of any extra items / additions, alterations / changes, the total amount May not exceed sanctioned amount. if it exceeds, prior approval is be taken from the User Department and Competent Authority.

22. Assistant Engineer (Civil)/Assistant Engineer (Electrical) has to enclose the work completion certificate and **No claim certificate** from the contractor to the final bill.

23. Certificate of satisfactory completion of work from user department and or Engineer in charge may be obtained and enclosed to the final bill for payment.

24. Further details if any can be had from the Office of the University Engineer, University of Hyderabad, Hyderabad-5000 046 during working hours.

25. GST invoice form should be filled and submitted along with the bill.

26. Labour engaged and working equipment brought to site by the contractor shall be recorded in the UoH Security main gate and necessary gate pass obtained before entering in to the premises.

**Signature of the Contractor**

**LIST SHOWING PREFERRED BRANDS/MANUFACTURERS/MAKE**

NOTE: - 1) A List of Preferred Brand Names of Various Materials / Products are shown below for usage in execution of Work. However, Approved equivalent material of any other Specialized Companies / Firms may also be used , in case it is established that the Brands Specified below are not available in the market and subject to Approval of the alternate Brand by the Engineer In charge.

2) It must be ensured, in general, that all materials to be used in the works shall bear BIS Certification mark. In cases where for a particular material/product, BIS Certification Mark is not available, then the material proposed to be procured can be used subject to the condition that it should conform to CPWD Specifications and relevant BIS codes. In such cases written approval of the Engineer-in -Charge shall be obtained before use of such material in their works.

3) The list given below does not absolve the Executing Agency from their responsibility for using these products. It is only after, they are satisfied about the quality and performance, the products shall be used. To achieve this, proper check on the quality of the product, actually to be used, should be exercised.

| S.No | Product | Make |
|---|---|---|
| 1 | Ordinary Portland Cement | ACC, Ultratech, Vikram, Shree Cement, Ambuja, Jaypee Cement, Century Cement, JK Cement, Penna Cement , Bharathi Cement, Maha , Nagarjuna and Brands Approved by CE(SZ)II,CPWD,Hyderabad. |
| 2 | Portland Pozzolana Cement | |
| 3 | White Cement | Birla, J.K. White, Travancore |
| 4 | Reinforcement steel – (Primary Producers) | RINL, SAIL, TATA STEEL Ltd., JSW STEEL Ltd., JINDAL STEEL & POWER Ltd., Shyam produced by M/s.Shyam Steel Industries Ltd and Manufacturers approved by Spl.DG(SR),CPWD,Chennai |
| 5 | Ready Mix Concrete (RMC) | Ultra Tech, ACC, RMC Ready Mix (India), Nuvoco Vistas Corporation Ltd., (formally known as Lafarge India Ltd.), RMC by M/s Aparna Enterprises limited,Hyderabad, RDC Concrete (India) Pvt. Ltd and additional firms approved by CE, SZ-II, CPWD, Hyderabad. |
| 6 | Pulverized Stone Sand/ Crushed Stone Sand (Manufactured Sand) | Rank Enterprises, Robo Sand. |
| 7 | Polymer based Curing Compounds | FOSROC, SIKA, BASF |
| 8 | Structural Steel Sections | TATA, SAIL,RINL, JINDAL Steel & Power Ltd., J SW |
| 9 | Hollow Steel Tube Sections | TATA, Jindal, Apollo |
| 10 | Fly ash Cement Bricks | KSP Industries, Prakash International Ltd, NUBRIC. |

**Signature of the Contractor**

| | | |
|---|---|---|
| 11 | Autoclaved Aerated Concrete Blocks (AAC) | M/s. Hyderabad Industries Ltd., M/s. Ultra Tech India Limited, M/s. Siporex India Ltd., NCL, NUBRIC. |
| 12 | Binding Wire | TATA, JSW |
| 13 | Factory Made Cement Concrete Cover Blocks | A.S.R. Cover Blocks, Stand alone Universal Concrete Cover Blocks |
| 14 | RCC Door Frames | Ventura, Bothra. |
| 15 | Flush Door Shutters | Raavela Doors, Indian Timber Products, Kitply, |
| 16 | Fire Check / Rated Doors | Navair, Godrej, Shaktimet, Kenwood, MPP Schodders. |
| 17 | Smoke Seal Strip | Promat, Astro flame |
| 18 | Plain / Prelaminated Particle Board | ECO Board, TESA Action Co., Kitlam, Archid ply, Century |
| 19 | Ply wood / Laminate | Kitply, Centuryply, Greenply, Merino, Sonear (Donear), Formica, Archidply, Royal touch . |
| 20 | Natural wood Veneers | Kitply, Centuryply, Sonear (Donear), Greenply Archidply, Durain, National Action Tesa, Anchor. |
| 21 | Adhesive / Glue | Pidilite, Dunlope, Sika, Fosroc, Vamorganic. |
| 22 | Steel Windows/ Pressed Steel Frames | Madhu Industries, (Bengaluru), San Harvic, NCL |
| 23 | Cement Bonded Particle Board | BISON Boards of NCL. |
| 24 | PVC Door Frames & Shutters | Rajshri Plastiwood, Sintex. |
| 25 | FRP Door Frames & Shutters | Meena Fibre Glass, Duroplast, Cactus, Polyline. |
| 26 | UPVC Windows | Fenesta, Kommerling , Rehau, Wintech, LG, Encraft – Madhu Industries, Polywood. |
| 27 | Ceramic Floor /Dado Tiles | Somany, Johnson, Kajaria, Orient, Bell, RAK, Asian, NITCO, AGL tiles. |
| 28 | Vitrified Tiles | Somany, Johnson, Kajaria, Orient Bell Ltd, RAK, Vitero brand Aparna tiles |
| 29 | Precast Terrazo Tiles | NITCO, Hindustan, Modern |
| 30 | Precast Chequered Tiles | NITCO, Hindustan, INDO, Bharat, Poddar. |
| 31 | Non Metallic Floor Surface Hardners | Ironite, Hardonite, FOSROC, SIKA, BASF, CICO, Pidilite. |
| 32 | Precast Cement Concrete Tiles | NITCO, Hindustan, INDO, Ultra, NTC, Poddar. |
| 33 | Factory made Cement Concrete Interlocking Paver Blocks | Earth Pavers Hyd. Pvt. Ltd., NITCO (Rockard), Bharat (Nilsan), Classic Tiles. |
| 34 | Grass Paver | Unistone, Ultra. |
| 35 | Glass Mosaic Tiles | Palladio, Coral, Mridul, Bisazza |

**Signature of the Contractor**

| | | |
|---|---|---|
| 36 | PVC Flooring | LG Hausys, Ger Flor, Armstrong . |
| 37 | High Density Fibre (HDF) Pre-laminated Flooring boards | Pergo, Armstrong. |
| 38 | Unglazed Heavy Duty Vitrified Tiles | Somany ( Dura Gres ), Kajaria (Pavigres). |
| 39 | Unglazed Heavy Duty Paver/Parking Tiles | Somany ( Dura Stone ), Johnson (Endura), |
| 40 | Clay Tiles on Roof | Kenjai, Johnson, Common Wealth Trust (Ind) Ltd |
| 41 | Tile Adhesives | Laticrete, ,Ardex Endura, Weber, Roff. SIKA, Ferrous. |
| 42 | Grout Compound/ Epoxy Grouts | Laticrete, Ardex Endura, Weber, Fosroc, Pidilite, SIKA, Ferrous, BASF, CICO. |
| 43 | Epoxy Motor | Fosroc, SIKA, BASF |
| 44 | Water Proofing Compound | Fosroc, CICO, SIKA, Pidilite, , BASF, Accoproof, Ardex Endura. |
| 45 | Damp Proof Material | Duraseal, Acco-proof, Impermo |
| 46 | Actactic Polypropylene (APP) Modified Water Proof Membrane | S T P, Bitumat Co. Ltd., Pidilite, Hydrotech Ltd. |
| 47 | Admixtures / Platisizers | Fosroc, CICO, SIKA, BASF, MC |
| 48 | Ethylene Propylene Diene Monomer (EPDM) Gasket | Hanu /Anand |
| 49 | Aluminium Extruded sections | Jindal, Hindalco, Indian Aluminium Co. |
| 50 | Polyester Powder Coating | Nerolac, Berger, Akzonobel, Jotun |
| 51 | Poly Sulphide Sealant | Pidilite, Tuffseal, Choksey chemicals. |
| 52 | Cement Based Wall putty | Birla Wall Care, J.K. Wall putty, Berger Paints , Asian Paints. |
| 53 | Paints/ Primer / Acrylic Emulsion (Premium Quality) | ICI Dulux, Asian Paints, Berger, Nerolac . |
| 54 | Melamine Polish | Asian Paints, Melamyne Gold Wudfin of Pidilite Industries, Timbertone of ICI Dulux. |
| 55 | Water Proofing Cement Paint | Snowcem India, ICI Dulux, Berger, Asian. |
| 56 | PU Enamel Metallic Paints on MS Structure & Epoxy paints (Premium Quality) | SKK, Akzonobel, Asian, Berger, MRF. |
| 57 | Calcium Silicate False Ceiling Tiles | Aerolite Co, Hilux, Armstrong |
| 58 | Gypsum Board False Ceiling Tiles | Saint Gobain, Lafarge, Amstrong Co. |
| 59 | Mineral Fibre Board False Ceiling Tiles | Armstrong , Decosonic. |
| 60 | Rockwool / Glasswool insulation. | Twigafiber, Llyod Insulation, Supreme. |
| 61 | False Flooring System . | Kebao, Pinnacle, Access Floor System |
| 62 | Anodised / Powder Coated Aluminium Fittings / Fixtures- | Everite, Jyoti, Shakti, Sigma (BIS mark), Hardima. |
| 63 | Stainless Steel Pipes (Railing) | Jindal Stainless Steel Ltd., Connect Architectural Products Pvt. Ltd. |

**Signature of the Contractor**

| | | |
|---|---|---|
| 64 | Stainless Steel Wire Mesh | Champion Make, GKD. |
| 65 | Float / Plain / Tinted / Tempered / Toughened Glass. | Modi, Saint Gobain, Asahi, Atul, Glaverbel, Pilkington . |
| 66 | Mirror Glass. | Modi Guard, Atul, Asahi, Goldenfish. |
| 67 | Hydraulic Door Closers / Floor Springs | Godrej, Hardwyn, Everite, Dorma, Dorset, Magnum, Kich. |
| 68 | Steel Nuts, Bolts and Screws- | Atul, Hilti, Kundan, Priya . |
| 69 | Ball Bearing Hinges and Spring Hinges | Dorma, Hafele, Geze, Dorset, Magnum. |
| 70 | Stainless Steel Screws | Kundan, Arrow, Nettlefold, GKW. |
| 71 | Clamping System Using Dash / Anchor Fastners. | Hilti, Fischer,Bosch, Canon. |
| 72 | Locks in Furniture Cabinets. | Hettich, Blum, Hafel, Godrej, Link, Harrison. |
| 73 | Four Point / Multi Point Locking Handle. | Hefele, Alu-Alfa, Geze, Dorma, Godrej . |
| 74 | Stainless Steel Friction stay hinges | Hafele, Earl Bihari |
| 75 | Door closer lock / Panic exit device | Ingersoll Rand, Dorma, Monarch. |
| 76 | Door Coordinator | UL Listed, Monarch. |
| 77 | Precoated Galvolume Iron Profile Sheets. | Pennar, TATA Blue scope, NCL. |
| 78 | Multi Walled PolyCarbonate Roofing Sheets | Lexan, GE |
| 79 | Bitumen | Indian Oil, Hindustan Petroleum Corporation. |
| 80 | Aluminium Composite Panels (ACP) | Alstrong, Alucobond, Aluplex, Alubond. |
| 81 | Structural Glazing | Modi, Saint Gobain, Asahi, Glaverbel. |
| 82 | Structural and Weather Sealants (Silicon) | Dow Corning, Wacker., GE, BASF |
| 83 | Adhesive Tape | Norton |
| 84 | Spider Patch Fittings for Structural Glazing | Dorma, Sevax, Kich, Ozone, Hafele. |
| 85 | G.I. Pipes - | TATA, Jindal, Zenith, Hissar . |
| 86 | G.I. Fittings | HB, R Brand, Unik, ICS. |
| 87 | Gun Metal Valves / Non Return Valves | Zoloto, Leader, Sant. |
| 88 | C.I. Sluice Valves (Double Flanged) | Zoloto, Leader, SANT, Kirloskar, IVC, Burn. |
| 89 | PTMT fittings/ fixtures | Prayag, Shakti, pearl. |
| 90 | C.P. Brass fittings/ fixtures | Jaquar , Marc, Plumber, ESS ESS, TOTO, Parko, Nova , Grohe. |
| 91 | C.P.V.C pipes & specials | Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex, Flowguard. |
| 92 | uPVC Pipes & Fittings. | Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex. |
| 93 | Poly Propylene Random Co polymer (PPR) Pipes & Specials | SFMC, Victus, Supreme , Prince. |

**Signature of the Contractor**

| | | |
|---|---|---|
| 94 | Centrifugally Cast (spun) Pipes & Fittings (Sanitary Pipes)/ Centrifugally Cast iron hub less pipes | NECO , HEPCO, SKF, Bengal Iron Corporation (BIC) / NECO, kepsilan |
| 95 | Centrifugally Cast (spun) Pipes (LA) & Fittings ( Water Supply Pipes) / | Electro steel, Kesoram, LANCO Industries, RIF, NECO./ NECO, kepsilan |
| 96 | Vitreous China Sanitary ware | Parryware, Neycer, Hindware, Cera, Jaquar, TOTO, Duravit. |
| 97 | Stainless Steel Sinks | Nirali, Kaff, Hindware, Johnson, Signature, Neelkanth, Cobra, Diamond. |
| 98 | Fire Clay Sinks | Sunfire, Parryware, Hindware. |
| 99 | Sensor Based Auto Flush Systems | A O S Systems, TOTO, Parryware, Hindware, Grohe, Kochler. |
| 100 | PVC Water Storage Tanks | Sintex, Uniplast, Durocon, Polycon, Supreme. |
| 101 | Float Valve (Ball Valve) | Prayag, Leader, Zoloto, IBP, Arco. |
| 102 | Water Meter | Zoloto, Leader, Dashmesh. |
| 103 | RCC Non Pressure (NP-2) Pipes - | Indo., Hindustan, Balaji Pipe Industries, Indian Hume Pipes Ltd. |
| 104 | Factory Made SFRC (RCC) Manhole Covers | Indo, Balaji Pipe Industries, Supreme. |
| 105 | CI Manhole Covers | SKF, HIF, Neco, Bengal Iron Corporation (BIC). |
| 106 | Coupler for reinforcement bars | LOKPAL Industries – Noida, Shree ISPAT Traders – Jaipur, Trimurthi Engg. & Fab Works – Nagpur, National cutting Tools Sai Couplings – Pune, SPROCS Rebar Couplings Kanva Trading – Chennai. |
| 107 | L.T. Power Cable | Finolex/ Universal/ Fort Gloster/ Polycab/ Havells |
| 108 | Modular switch, socket power | TOYONA (Accura) Anchor ( Roma) |
| | Socket TV Telephone Socket | |
| 109 | Modular switch, socket power | TOYONA (Accura) Anchor ( Roma) |
| 110 | CFL Lamps & Fittings | Havells/Philips/Crompton |

111. **ELECTRICAL**

1. L.T. Power Cable : Finolex/ Universal/ Havells/ Polycab
2. H.T. XLPE Cable :Universal/Polycab/Havells/Asian Asian
3. Multi stand flexible copper wires : finolex/Anchor/Havells/Polycab.
4. Modular switch, socket power : TOYONA (Accura) Anchor ( Roma) Socket TV Telephone Socket
5. Modular piano type switch :TOYONA (Accura) Anchor ( Roma)
6. Fan regulators : TOYONA (Accura)
7. Cable Glands : Comet / Jainson
8. Cable lungs copper : Dowells/ Jainson
9. L.T.Switch Gear & MCCB : Schneider/ MDS/ Siemen's/ C & S/ Legrand/ L & T
10. MCB'sRMCB's etc. : Schneider / MDS/ Siemen's/ C & S/ Legrand/ L & T
11. Protection Relays : Alshthom/Segc/Telimachine
12. Panel meters 96 sqm( Digital) : Enercon/Neptune
13. Panel meters 144 sqm( Analong) : AE/MECO
14. Indication lamps led type : Binay/Schnieder Push buttons

**Signature of the Contract**

15. Sector Switches : Kaycee/Salzer/TOYOMA (Accura)
16. Distribution Boards : Protec/MDS
17. PVC pipes : Sudhakar/Finolex/Mercury
18. PVC Fittings : Prime/Mercury
19. Tube light fitting : Crompton/Philips/Bajaj
20. Switches/Sockets : Anchor (Rona),TOYOMA (Accura)/Bajaj
21. Electronic Fan regulators : Anchor (Rona),TOYOMA (Accura)
22. Telephone wires : Mazda
23. T.V.Wire : Finolex/Anchor
24. CFL Lamps & Fittings : Bajaj/Philips/Crompton
25. Ceiling fans : Crompton/Bajaj/Orient/Usha
26. Exhaust fans : Crompton/GEC/Khaitan
27.Sodium vapor lamps &fittings : Bajaj/Philips/Crompton
28. Energy meter : Havells/ L & T/ECE
29. Transformers : Kirloskar. Crompton Grieves/Indotech/Alstom/PETE
30. Vacuum circuit breakers : Bieccola wire/ Alshthom/CG
31.Cubical Electrical panels : Any fabrication with CPRI approved and ISO : 9002Bus ducts/Generator Panel certification company/ Manufacturer.
32. Submersible pump motor : Texmo / CRI / KSB for borewells
33. Monoblock/ open well motor : Texmo / CRI /Kirloskar/Crompton Pumps
34. Cable Joint/ Termination Kits : Reychem/ Denson/ 3m

**Signature of the Contractor**

| Name of work: "Providing Internal Electrification to the Lab in CIS building in University of Hyderabad campus—Reg.. | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1) The estimates amount is inclusive of GST.<br>2) The bidder should quote basic rates exclusive of GST and quote GST percentage separately; GST should be revised from time to time. | | | | | | | | | |
| **S.No** | **DSR No.** | **Description of items** | **Qty** | **Unit** | **Basic Rate in Figures to be entered by the Bidder without GST** | **Add: GST (%)** | **Total Amount without GST** | **Total Amount with GST** | **Total Amount with GST in words** |
| | | | | | | | | | |
| 1 | 1 | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit incl removing old wiring as required. 3 x 4 sq. mm | 426 | Mtr | | | | | |
| 2 | 1.21 | Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. 25 mm | 62 | Mtr | | | | | |
| | 1.21.3 | 32 mm | 150 | Mtr | | | | | |
| 3 | MR | Wiring for light/ power plug with 2X6 sq. mm FRLS PVC insulated copper conductor single core cable in existing surface/ recessed steel/ PVC conduit along with 1 No 6 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required. | 120 | Mtr | | | | | |
| 4 | 1.24 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 5/6 amps switch | 141 | Each | | | | | |
| | 1.24.3 | 15/16 amp switch | 141 | Each | | | | | |
| | 1.24.4 | 3 pin 5/6 amp socket outlet | 283 | Each | | | | | |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | 1.24.5 | 6 pin 15/16 amp socket outlet | 141 | Each | | | | | |
| 5 | 1.28 | Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required. 8 Module | 141 | Each | | | | | |
| 6 | 2.2 | Providing and fixing following rating and breaking capacity and pole MCCB withthermomagneticreleaseandtermin alspreadersinexistingcubiclepanel board including drilling holes in cubicle panel, making connections, Ics=100% Icu and Operational Voltage 690V etc. as required. 100 A, 16 KA,TPMCCB | 1 | Each | | | | | |
| 7 | 2.3 | Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 8 way , Double door | 5 | Each | | | | | |
| 8 | 2.4 | Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. incl dismantling old DB as required. (But without MCB/RCCB/Isolator) 4 way (4 + 12), Double door | 1 | Each | | | | | |
| 9 | 2.10 | Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning | 42 | Each | | | | | |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | | etc. as required. Single pole | | | | | | | |
| | 2.10.3 | Double pole | 5 | Each | | | | | |
| 10 | MR | Supply and fixing 63 A 4 pole, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make:- Legrand/L&T/Philiphs. | 1 | Each | | | | | |
| 11 | MR | Supply of 3.5 core x 25 sqmm XLPE insulated Aluminium Armoured cable of 1.1 KV grade etc as required. Make: Finolex/Polycab/Havells. | 60 | Mtr | | | | | |
| 12 | MR | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of upto 35Sqmm size in medium class 40mm PVC conduit along with accessories on wall surface (clamped with 1mm thick saddle) as required. | 60 | Mtr | | | | | |
| 13 | 11.1 | Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5 X 25 sq. mm (28mm) | 2 | Each | | | | | |
| 14 | MR | Supply and fixing of following sizes of uPVC Trunking integral cable management system on surface including all accessories complete as required. | | | | | | | |
| | | 50MM X 50MM | 50 | mtrs | | | | | |
| | B | **Civil DSR Item:-** Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm (31 x 0.08 = 2.4) | 2.48 | sqm | | | | | |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 15 | 15.23 | | | | | | | | |
| 16 | 4.1 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand(zone-III) including manufactured sand derived from Recycled concrete aggregate (RCA) up to 25% : 4 graded stone aggregate 20 mm nominal size including Recycled Concrete Aggregate (RCA) upto 25% ) (31 x 0.075 x 0.08 =0.18) | 0.186 | Cum | | | | | |
| 17 | 15.2 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) (31 x 0.05 x 0.08 =0.12) | 0.124 | Cum | | | | | |

**Signature of the Contractor** **Sd/-** **University Engineer** **Sd/-** **Assistant Engineer (E)** **Sd/-** **D'M Grade-I**