UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 21.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **27.10.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 27.10.2025 upto 12.00 PM

Opening of Quotations:- 27.10.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Providing and fixing of damaged Pre-cast slabs for closing open drain at MH-J&K Kitchen in UoH campus	Rs. 49,400/-

Sd/-
Executive Engineer A/C

Name of work:- Providing and fixing of damaged precast slabs for closing open drain at MH-J&K kitchen in UoH campus

1) The Bidder should quote rates inclusive of GST.
2) All the below item rates are all inclusive of GST.

SCHEDULE OF QUANTITIES

S.No	D.S.R. No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	5.15	Providing, transporting, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete in lintels, beams and bressumers, including setting in cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering and shuttering but, excluding the cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand(zone- III)derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	1.80	Cum	Figure Rs_____ Words Rupees_____ _____	
2	5.22 5.22A.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	150.00	Kg	Figure Rs_____ Words Rupees_____ _____	
3	2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared.	544.00	Sqm	Figure Rs_____ Words Rupees_____ _____	
					Total Amount in figures Rs.	

Less Rebate Offered if any_____
Net Amount_____
Total Amount in words(Including GST) _____

Sd/-

Signature of the Contractor **Executive Engineer A/C**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-

Executive Engineer (A/C)

CC to:

1. A.E. Sub-Division (Civil-II)
2. Office Copy