UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 11.06.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **16.06.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 16.06.2025 upto 12.00 PM

Opening of Quotations:- 16.06.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Providing internal painting and replacement of door at B-10 Qtr in UoH campus	Rs. 46,300/-

Sd/-
Assistant Engineer (Civil)

Name of work: Maintenance of Building: -"Providing internal painting and Replacement of door at B-10 Quarter" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	13.81.1	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade. Old work (one or more coats). Make: ICI Dulux/ Asian paints (Apcolite)/ Berger/ Nerolac.	460.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
2	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	230.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
3	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work. Make: ICI Dulux/ Asian paints (Apcolite)/ Berger/ Nerolac.	70.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

4	15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
5	9.21.2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.10	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
6	9.96.1	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete : 300x16 mm. . Make: Hardima/ Everite/ Sigma/ Jyothi.	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
7	9.97.4	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	

		: 150x10 mm. Make: Hardima/ Everite/ Sigma/ Jyothi.				
8	9.100.1	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : 125 mm. Make: Hardima/ Everite/ Sigma/ Jyothi.	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
9	13.62.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. Make: ICI Dulux/ Asian paints (Apcolite)/ Berger/ Nerolac.	5.05	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Sd/-
Assistant Engineer (Civil)

Signature of the Contractor

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Assistant Engineer (Civil)

CC to:
1. A.E. Sub-Division (Civil-II)
2. Office Copy